

S. No.	Description of a structural member	Time Period	Checked
1	Walls, columns, and vertical sides of beams	1 to 2 days	
2	Slabs (props left under)	3 days	
3	Beam soffits (props left under)	7 days	
4	Removal of props to slabs		
(a) For slabs spanning upto 4.5 m		7 days	
(b) For slabs spanning over 4.5 m		14 days	
5	Removal of props to beams and arches		
(a) Spanning upto 6 m		14 days	
(b) spanning over 6 m		21 days	